SP4000 PCB Layout



40VA transformer strongly recommended

This equipment must be installed and maintained by qualified service personnel only. For UL and C-UL warnings, refer to the UL and C-UL Warnings section at the back of the SP4000 Reference & Installation Manual.

Max. number of keypads = 15 keypads Max. aux. current = 650 mA

Max. distance of keypad from panel = 76m (250 feet)

Max. total run of wire = 230m (750 feet)